

PROPERTY OWNER / APPLICANT
 HILLSMERE SHORES IMPROVEMENT ASSOCIATION
 P.O. BOX 3485
 ANNAPOLIS, MD 21403
 EMAIL: marino@hillsmershores.org

PROPERTY ADDRESS:
 133 C BAY VIEW DRIVE
 ANNAPOLIS, MD 21401

PROPERTY SIZE: 1.0 ACRES

APPLICANT
 ARUNDEL RIVERS FEDERATION
 2822 SOLOMONS ISLAND RD., SUITE 202
 EDGEWATER, MD 21037
 PHONE #: 410-224-3802

DESIGN CONSULTANT
 ENVIRONMENTAL SYSTEMS ANALYSIS, INC.
 2141 PRIEST BRIDGE DR., SUITE 1
 CROFTON, MD 21114
 PHONE #: 410-267-0495

GENERAL NOTES:

1. PROPERTY BOUNDARIES, TOPOGRAPHY OUTSIDE OF PROJECT AREA AND EXISTING STRUCTURES SHOWN ARE TAKEN FROM ANNE ARUNDEL COUNTY GIS, ACCESSED IN NOVEMBER, 2022
2. SHORELINE FEATURES, TOPOGRAPHY AND BATHYMETRY WAS SURVEYED BY SUSTAINABLE SCIENCE, LLC IN NOVEMBER 2022.
3. VERTICAL DATUM: MLW = 0.0' (NAVD88: MLW = -0.32' MWH = 0.65')
4. HORIZONTAL DATUM: NAD83/2011
5. THE PROPERTY LIES WITHIN THE LIMITED DEVELOPMENT AREA (LDA) OF THE ANNE ARUNDEL COUNTY CRITICAL AREA
6. PER FEMA FLOOD MAP 24003C0261F, FLOODZONE AE EXTENDS TO THE 6 FOOT ELEVATION.

SITE DATA:

ZONING: MA1 – COMMUNITY MARINA
 MDE TRACKING NUMBER:
 TOTAL SITE AREA: 1.0 ACRES

MEAN HIGH WATER LINE (MHWL): 0.97
 MEAN LOW WATER LINE (MLWL): 0.00
 DISTURBED AREA (LOD): 0.32 AC. (13,967 SF)
 AREA VEGETATIVELY STABILIZED: 0.16 AC. (6,895 SF)
 AREA PERMANENTLY STABILIZED: 0.32 AC.
 PROPOSED CUT: 0 CY
 PROPOSED FILL: 3963 CY
 (SAND FILL = 3227 CY, ROCK FILL = 736 CY)
 EXCESS SPOIL TO BE REMOVED: 0 CY
 BORROW TO BE PLACED ON SITE: 3963 CY

NOTE: THIS PROJECT CONSISTS ENTIRELY OF SAND AND ROCK FILL. WHEN POSSIBLE, EXISTING ROCK WILL BE REUSED IN THE PROPOSED STONE STRUCTURES.

HILLSMERE SHORES COASTAL RESILIENCY PROJECT

ANNE ARUNDEL COUNTY, MARYLAND

APRIL, 2023



AERIAL IMAGE

SCALE: 1"=100'



VICINITY MAP

SCALE: 1"=2000'

CONSULTANT'S CERTIFICATION

THE DEVELOPER'S PLAN TO CONTROL SILT AND EROSION IS ADEQUATE TO CONTAIN THE SILT AND EROSION ON THE PROPERTY COVERED BY THE PLAN. I CERTIFY THAT THIS PLAN OF EROSION AND SEDIMENT CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THIS SITE, AND WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE AASCD PLAN SUBMITTAL GUIDELINES AND THE CURRENT MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL. I HAVE REVIEWED THIS EROSION AND SEDIMENT CONTROL PLAN WITH THE OWNER/DEVELOPER.

MD P.E. LICENSE # _____
 MD LAND SURVEYOR LICENSE # _____
 MD LANDSCAPE ARCHITECT # _____
 NAME _____
 FIRM NAME _____
 ADDRESS _____
 CITY _____ STATE ____ ZIP CODE _____

SEQUENCE OF CONSTRUCTION:

1. NOTIFY THE DEPARTMENT OF INSPECTIONS AND PERMITS (410-222-7780) AT LEAST 48 HOURS BEFORE COMMENCING WORK. WORK MAY NOT COMMENCE UNTIL THE PERMITEE OR THE RESPONSIBLE PERSONNEL HAVE MET ON SITE WITH THE SEDIMENT AND EROSION CONTROL INSPECTOR TO REVIEW THE APPROVED PLANS. (1 DAY)
2. NOTIFY MARYLAND DEPARTMENT OF THE ENVIRONMENT INSPECTION AND COMPLIANCE PROGRAM (410-537-3510) AT LEAST FIVE DAYS PRIOR TO THE START OF CONSTRUCTION. NOTIFY THE COUNTY CM/ AT LEAST 2 WEEKS PRIOR TO BEGINNING WORK.
3. NOTIFY MISS UTILITY (1-800-257-7777) A MINIMUM OF 48 HOURS PRIOR TO THE START OF WORK. (1 DAY)
4. CONDUCT A PRE-CONSTRUCTION MEETING. WORK MAY NOT COMMENCE UNTIL THE PERMITEE OR THE RESPONSIBLE PERSONNEL HAVE MET ON SITE WITH THE SEDIMENT AND EROSION CONTROL INSPECTOR TO REVIEW THE APPROVED PLANS. (1 DAY)
5. THE LIMITS OF DISTURBANCE (LOD) MUST BE FIELD-MARKED USING STAKES AND FLAGGING PRIOR TO CLEARING OF TREES, INSTALLATION OF SEDIMENT CONTROL MEASURES, CONSTRUCTION OR OTHER LAND DISTURBING ACTIVITIES AS SHOWN ON THE GRADING PLAN. THE LIMITS OF DISTURBANCE AND EXISTING CONDITIONS MUST BE APPROVED BY THE SEDIMENT CONTROL INSPECTOR PRIOR TO COMMENCING WORK. CLEAR THE MINIMUM AREA NECESSARY TO INSTALL SEDIMENT CONTROL AND THE STAGING AREA.
6. TEMPORARY AND PERMANENT STABILIZATIONS OF DISTURBED AREAS WILL BE REQUIRED THROUGHOUT CONSTRUCTION AS MANDATED BY EROSION AND SEDIMENT CONTROL REGULATIONS.
7. INSTALL STABILIZED CONSTRUCTION ENTRANCE (SCE). (1 DAY)
8. ESTABLISH THE STOCKPILE AREA ACCORDING TO THE ESC PLANS. THIS AREA IS TO BE FOR TEMPORARY USE ONLY. ALL EXCAVATED MATERIAL SHOULD BE DEPOSITED AND STABILIZED IN AN APPROVED AREA.
9. INSTALL TURBIDITY CURTAIN. ALL NECESSARY EROSION AND SEDIMENT CONTROL (ESC) AND TREE PROTECTION MEASURES MUST BE INSTALLED PRIOR TO THE COMMENCEMENT OF GRADING WORK. THESE CONTROLS AND DEVICES MUST BE MAINTAINED THROUGH THE CONSTRUCTION PROCESS AND UNTIL THE SITE IS STABILIZED. (5 DAYS)
10. ONCE SEDIMENT CONTROLS HAVE BEEN INSTALLED, CONTACT THE SEDIMENT CONTROL INSPECTOR FOR APPROVAL OF THE SEDIMENT CONTROL INSTALLATION PRIOR TO COMMENCING WORK. INSPECTIONS AND PERMITS MAY ALSO REQUIRE THAT AN INSPECTION AND CERTIFICATION OF THE INSTALLATION OF SEDIMENT CONTROL BE PERFORMED BY A DESIGN PROFESSIONAL PRIOR TO CONSTRUCTION COMMENCING. (1 DAY)
11. BEGIN REMOVING AND STOCKPILING EXISTING STONE FOR USE IN THE NEW PROPOSED STRUCTURES, ONLY REMOVING WHAT IS NEEDED FOR CONSTRUCTION AT THAT TIME.
12. INSTALL STONE STRUCTURES A, B, C, AND D BASED ON THE LOCATIONS, ELEVATIONS, AND DESIGN SPECIFICATIONS SHOWN ON THE PLANS. (20 DAYS)
 - a. LAY GEOTEXTILE ON EXISTING GRADE TO COVER THE ENTIRE BOTTOM OF THE HEADLAND STRUCTURE AND ENOUGH TO WRAP AROUND THE SIDE OF THE STRUCTURE. HEADLAND STRUCTURE SHALL TIE INTO EXISTING GRADE.
 - b. PLACE LARGEST BOULDERS FOR THE STRUCTURE ON TOP OF THE GEOTEXTILE SUCH THAT EACH BOULDER IS IN CONTACT WITH ITS NEIGHBOR AND FORMS A RELATIVELY FLAT SURFACE. ARRANGE BOULDERS AS NECESSARY TO MINIMIZE VOID SPACE WITHIN THE FOOTER LAYER.
 - c. PLACE A LAYER OF SMALLER BOULDERS ATOP THE FOOTER BOULDERS SUCH THAT THEY ARE STABLE AND INTERLOCK WITH THEIR NEIGHBOR AND THE FOOTER LAYER. USE RECYCLED EXISTING WEATHERED STONE ALONG EXTERIOR OF THE STRUCTURE AS MUCH AS POSSIBLE TO BLEND INTO THE LANDSCAPE BETTER. ALL BOULDERS ARE TO BE INDIVIDUALLY PLACED TO CREATE A STABLE, UNIFORM STRUCTURE IN WHICH VOIDS ARE MINIMIZED.
 - d. CHINK VOIDS.
 - e. WRAP WOVEN GEOTEXTILE AROUND LANDWARD SIDE OF THE HEADLAND STRUCTURE TO PROPOSED SAND/COBBLE ELEVATION. TRIM ANY EXPOSED GEOTEXTILE.
 - f. THE ALLOWABLE VERTICAL TOLERANCE ON ALL ELEVATIONS IS +/- 0.1 FEET.
13. CONCURRENT WITH THE INSTALLATION OF THE STONE STRUCTURES, MIX AND PLACE COBBLE / SAND SO AS TO COVER THE EXPOSED WALL WHERE STONE WAS REMOVED AND AS NECESSARY TO CONSTRUCT THE STONE STRUCTURES. (10 DAYS)
 - a. STOCKPILE WASHED COBBLE AND WASHED COARSE SAND (CONCRETE SAND) IN ACCORDANCE WITH THE APPROVED PLAN SET.
 - b. USING TRACKED EXCAVATION EQUIPMENT, SEQUENTIALLY PLACE FOUR (4) BUCKETS OF COARSE SAND AND ONE (1) BUCKET OF WASHED COBBLE INTO DUMP TRUCK UNTIL TRUCK IS FILLED.
 - c. DUMP LOAD INTO COBBLE / SAND ZONE THEN GRADE WITH DOZER TO ACHIEVE DESIGN GRADES AND INCLINATIONS.
14. INSTALL PLANTS PER PLANS, AT LEAST ONE MONTH (INCLUDING ONE STORM EVENT) AFTER COMPLETION OF THE SAND DUNES. INSTALL THE PROPOSED SHRUBS AS SPECIFIED ON THE PLANS. INSTALL GOOSE EXCLUSIONARY FENCING OVER PLANT ZONE. (7 DAYS)
15. REMOVE TRASH AND ALL EXCESS CONSTRUCTION MATERIALS FROM THE PROJECT SITE. (3 DAYS)
16. CONDUCT FINAL INSPECTION PRIOR TO DE-MOBILIZING FROM THE SITE. REPAIR AND ADDRESS ANY DEFICIENCIES IDENTIFIED DURING THE FINAL INSPECTION WITHIN 5 DAYS OF RECEIPT OF PUNCH LIST. (6 DAYS)
17. UPON APPROVAL OF COUNTY INSPECTOR, REMOVE SEDIMENT AND EROSION CONTROLS. (1 DAY)

STANDARD RESPONSIBILITY NOTES

I (WE) CERTIFY THAT:


- a. ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE IN ACCORDANCE WITH THIS SEDIMENT AND EROSION CONTROL PLAN, AND FURTHER, AUTHORIZE THE RIGHT OF ENTRY FOR PERIODIC ON-SITE EVALUATION BY THE ANNE ARUNDEL SOIL CONSERVATION AASCD BOARD OF SUPERVISORS OR THEIR AUTHORIZED AGENTS.
 - b. ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE FROM THE MARYLAND DEPARTMENT OF THE ENVIRONMENT'S APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT.

RESPONSIBLE PERSONNEL ON SITE: _____
 - c. IF APPLICABLE, THE APPROPRIATE ENCLOSURE WILL BE CONSTRUCTED AND MAINTAINED ON SEDIMENT BASIN(S) INCLUDED IN THIS PLAN. SUCH STRUCTURE(S) WILL BE IN COMPLIANCE WITH THE ANNE ARUNDEL COUNTY CODE.
2. THE COUNTY IS RESPONSIBLE FOR THE ACQUISITION OF ALL EASEMENTS, RIGHT, AND/OR RIGHTS-OF-WAY THAT MAY BE REQUIRED FOR THE SEDIMENT AND EROSION CONTROL PRACTICES, STORMWATER MANAGEMENT PRACTICES AND THE DISCHARGE OF STORMWATER ONTO OR ACROSS ADJACENT OR DOWNSTREAM PROPERTIES INCLUDED IN THE PLAN.
 3. FOR INITIAL SOIL DISTURBANCE OR RE-DISTURBANCE, PERMANENT AND/OR TEMPORARY STABILIZATION PER THE AASCD VEGETATIVE ESTABLISHMENT SHALL BE COMPLETED WITHIN THREE CALENDAR DAYS FOR THE SURFACE OF ALL CONTROLS, DIKES, SWALES, DITCHES, PERIMETER SLOPES AND ALL SLOPES GREATER THAN 3 HORIZONTAL TO 1 VERTICAL (3:1); AND SEVEN DAYS FOR ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE.
 4. THE GRADING AND SEDIMENT CONTROL APPROVAL ON THIS PLAN EXTENDS ONLY TO THOSE AREAS WITHIN THE LIMITS OF DISTURBANCE.
 5. THE APPROVAL OF THIS PLAN FOR SEDIMENT AND EROSION CONTROL DOES NOT RELIEVE THE DEVELOPER / CONSULTANT FROM COMPLYING WITH FEDERAL, STATE OR COUNTY REQUIREMENTS PERTAINING TO ENVIRONMENTAL ISSUES.
 6. THE COUNTY MUST REQUEST THAT THE SEDIMENT AND EROSION CONTROL INSPECTOR APPROVE WORK COMPLETED IN ACCORDANCE WITH THE APPROVED EROSION AND SEDIMENT CONTROL PLAN, THE GRADING OR BUILDING PERMIT, AND THE ORDINANCE.
 7. ALL MATERIAL SHALL BE TAKEN TO A SITE WITH AN APPROVED SEDIMENT AND EROSION CONTROL PLAN.
 8. FIRST PHASE INSPECTION AND APPROVAL OF THE SEDIMENT AND EROSION CONTROL INSPECTOR SHALL BE REQUIRED UPON COMPLETION OF THE INSTALLATION OF EROSION AND SEDIMENT CONTROLS PRIOR TO PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR GRADING. OTHER BUILDING OR GRADING INSPECTION APPROVALS MAY NOT BE AUTHORIZED UNTIL THE INITIAL APPROVAL BY THE SEDIMENT AND EROSION CONTROL INSPECTOR IS GIVEN. INSPECTION AND PERMITS MAY ALSO REQUIRE THAT AN INSPECTION AND CERTIFICATION OF THE INSTALLATION OF SEDIMENT CONTROLS ALSO BE PERFORMED BY A DESIGN PROFESSIONAL PRIOR TO CONSTRUCTION COMMENCING.
 9. APPROVAL FROM THE INSPECTOR MUST BE REQUESTED ON FINAL STABILIZATION OF ALL SITES PRIOR TO REMOVAL OF SEDIMENT AND EROSION CONTROLS.
 10. EXISTING TOPOGRAPHY MUST BE FIELD VERIFIED BY RESPONSIBLE PERSONNEL TO THE SATISFACTION OF THE SEDIMENT CONTROL INSPECTOR PRIOR TO COMMENCING WORK.

SIGNATURE OF DEVELOPER / OWNER _____ DATE _____

PRINT: NAME: _____
 TITLE: _____
 AFFILIATION: _____
 ADDRESS: _____
 TELEPHONE #: _____
 EMAIL: _____

MISS UTILITY



BEFORE YOU DIG CALL
 800-281-4777
 PROTECT YOURSELF. GIVE TWO
 WORKING DAYS NOTICE


THIS DRAWING DOES NOT INCLUDE NECESSARY COMPONENTS FOR CONSTRUCTION SAFETY. ALL CONSTRUCTION MUST BE DONE IN COMPLIANCE WITH THE OCCUPATIONAL SAFETY AND HEALTH ACT OF 1970 AND ALL RULES AND REGULATIONS THEREO APPURTENANT.

THE CONTRACTOR TO CALL MISS UTILITY TO HAVE ALL EXISTING UTILITIES MARKED 48 HOURS PRIOR TO ANY CONSTRUCTION.

INDEX OF SHEETS

SHEET 1	COVER SHEET
SHEET 2	EXISTING CONDITIONS
SHEET 3	GRADING / EROSION & SEDIMENT CONTROL PLAN
SHEET 4-5	EROSION & SEDIMENT CONTROL DETAILS
SHEET 6-7	PLANTING / BUFFER MANAGEMENT PLAN

REVISIONS			
NO.	BY	DATE	DESCRIPTION

Survey:

 Sustainable Science, LLC
 410 S. Second Street
 Denton, MD 21629
 phone: (410) 924-4316

Prepared for/Applicant:
 Hillsmere Shores Improvement Association (HSIA)
 P.O. Box 3485
 Annapolis, MD 21043


Prepared by:

 Environmental Systems Analysis, Inc.
 Natural Resources Management
 Ecological Restoration
 2141 Priest Bridge Drive, Suite 1
 Crofton, Maryland 21114

COVER SHEET
HILLSMERE SHORES COASTAL RESILIENCY PROJECT
 MAP 0057, GRID 0013, PARCEL 0159, SUBDIVISION 412
 2ND ELECTION DISTRICT, ANNE ARUNDEL COUNTY, MD


SCALE:
 DATE: APRIL, 2023
 ESA PROJECT NAME: 22587
 HILLSMERE MARINA LIVING SHORELINE
 SHEET: 1 of 7

- LEGEND**
- EX. PROPERTY BNDRY
 - - - EX. MAJOR CONTOUR
 - - - EX. MINOR CONTOUR
 - x - EX. FENCE LINE
 - ~ ~ ~ EX. TREE / SHRUB LINE
 - ○ ○ EX. VEGETATION (ALL EXISTING TREES & GRASSES TO REMAIN)
 - ▒ ▒ ▒ EX. ROCK / REVETMENT



April 2023 FILE: T:\NEWPROJ\2022\22587 Hillsmere Marina Shoreline\CAO\Plans\Grading Permit Plans\Sheet 2 - Ex. Conditions.dwg

REVISIONS			
NO.	BY	DATE	DESCRIPTION

Survey:

Sustainable Science, LLC
 410 S. Second Street
 Denton, MD 21629
 phone: (410) 924-4316


Prepared for/Applicant:
Hillsmere Shores Improvement Association (HSIA)
 P.O. Box 3485
 Annapolis, MD 21043


Prepared by:

Environmental Systems Analysis, Inc.
 Natural Resources Management
 Ecological Restoration
 2141 Priest Bridge Drive, Suite 1
 Crofton, Maryland 21114

EXISTING CONDITIONS
HILLSMERE SHORES COASTAL RESILIENCY PROJECT
 MAP 0057, GRID 0013, PARCEL 0159, SUBDIVISION 412

2ND ELECTION DISTRICT, ANNE ARUNDEL COUNTY, MD


 NORTH


 SCALE: 1"=30'

SCALE: 1"=30'
 SHEET: 2 of 7

April 2023 FILE: T:\NEWPROJ\2022\22587 Hillsmere Marina Shoreline\Grading\Permit Plans\Sheet 3 - Proposed Conditions.dwg

LEGEND

- EX. PROPERTY BNDY
- EX. MAJOR CONTOUR
- EX. MINOR CONTOUR
- - - EX. FENCE LINE
- x - EX. TREE / SHRUB LINE
- EX. VEGETATION (ALL EXISTING TREES & GRASSES TO REMAIN)
- ▨ EX. ROCK / REVETMENT
- EX. MHWL / MLWL
- PROPOSED MAJOR CONTOUR
- PROPOSED MINOR CONTOUR
- ▨ PROPOSED ROCK STRUCTURE
- ▨ SAND / COBBLE FILL
- LOD LIMIT OF DISTURBANCE
- SF SILT FENCE
- TPF TREE PROTECTION FENCE
- TC TURBIDITY CURTAIN
- ▨ STABILIZED CONSTRUCTION ENTRANCE
- ▨ PROPOSED WOODY DEBRIS

STRUCTURE TABLES

STRUCTURE A

NO.	CENTERLINE NORTHING (FT)	CENTERLINE EASTING (FT)	CREST EL.
1	460051	1458045	3.0'

STRUCTURE B




NO.	CENTERLINE NORTHING (FT)	CENTERLINE EASTING (FT)	CREST EL.
1	460018	1458082	3.0'
2	460005	1458118	3.0'
3	460006	1458162	3.0'

STRUCTURE C

NO.	CENTERLINE NORTHING (FT)	CENTERLINE EASTING (FT)	CREST EL.
1	460114	1458347	3.0'
2	460140	1458373	3.0'
3	460149	1458410	3.0'

STRUCTURE D

NO.	CENTERLINE NORTHING (FT)	CENTERLINE EASTING (FT)	CREST EL.
1	460257	1458596	3.0'
2	460280	1458610	3.0'



REVISIONS

NO.	BY	DATE	DESCRIPTION

Survey:

Sustainable Science, LLC
 410 S. Second Street
 Denton, MD 21629
 phone: (410) 924-4316

Prepared for/Applicant:
Hillsmere Shores Improvement Association (HSIA)
 P.O. Box 3485
 Annapolis, MD 21043

Prepared by:

Environmental Systems Analysis, Inc.
 Natural Resources Management
 Ecological Restoration
 2141 Priest Bridge Drive, Suite 1
 Crofton, Maryland 21114

GRADING / EROSION & SEDIMENT CONTROL PLAN
HILLSMERE SHORES COASTAL RESILIENCY PROJECT
 MAP 0057, GRID 0013, PARCEL 0159, SUBDIVISION 412


2ND ELECTION DISTRICT, ANNE ARUNDEL COUNTY, MD

SCALE: 1"=30'

DATE: APRIL, 2023
 ESA PROJECT NAME: 22587
 HILLSMERE MARINA LIVING SHORELINE
 SHEET: 3 of 7

DETAIL B-1 STABILIZED CONSTRUCTION ENTRANCE

STANDARD SYMBOL
SCE



CONSTRUCTION SPECIFICATIONS




- PLACE STABILIZED CONSTRUCTION ENTRANCE IN ACCORDANCE WITH THE APPROVED PLAN. VEHICLES MUST TRAVEL OVER THE ENTIRE LENGTH OF THE SCE. USE MINIMUM LENGTH OF 50 FEET (43 FEET FOR SINGLE RESIDENCE LOT). USE MINIMUM WIDTH OF 10 FEET. FLARE SCE 10 FEET MINIMUM AT THE EXISTING ROAD TO PROVIDE A TURNING RADIUS.
- PIPE ALL SURFACE WATER FLOWING TO OR DIVERTED TOWARD THE SCE UNDER THE ENTRANCE. MAINTAINING POSITIVE DRAINAGE. PROTECT PIPE INSTALLED THROUGH THE SCE WITH A MOUNTABLE BERM WITH 5:1 SLOPES AND A MINIMUM OF 12 INCHES OF STONE OVER THE PIPE. PROVIDE PIPE AS SPECIFIED ON APPROVED PLAN. WHEN THE SCE IS LOCATED AT A HIGH SPOT AND HAS NO DRAINAGE TO CONVEY, A PIPE IS NOT NECESSARY. A MOUNTABLE BERM IS REQUIRED WHEN SCE IS NOT LOCATED AT A HIGH SPOT.
- PREPARE SUBGRADE AND PLACE NONWOVEN GEOTEXTILE, AS SPECIFIED IN SECTION H-1 MATERIALS.
- PLACE CRUSHED AGGREGATE (2 TO 3 INCHES IN SIZE) OR EQUIVALENT RECYCLED CONCRETE (WITHOUT REBAR) AT LEAST 6 INCHES DEEP OVER THE LENGTH AND WIDTH OF THE SCE.
- MAINTAIN ENTRANCE IN A CONDITION THAT MINIMIZES TRACKING OF SEDIMENT. ADD STONE OR MAKE OTHER REPAIRS AS CONDITIONS DEMAND TO MAINTAIN CLEAN SURFACE. MOUNTABLE BERM, AND SPECIFIED DIMENSIONS. IMMEDIATELY REMOVE STONE AND/OR SEDIMENT SPILLED, DROPPED, OR TRACKED ONTO ADJACENT ROADWAY BY VACUUMING, SCRAPING, AND/OR SWEEPING. WASHING ROADWAY TO REMOVE MUD TRACKED ONTO PAVEMENT IS NOT ACCEPTABLE UNLESS WASH WATER IS DIRECTED TO AN APPROVED SEDIMENT CONTROL PRACTICE.

MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL

U.S. DEPARTMENT OF AGRICULTURE NATURAL RESOURCES CONSERVATION SERVICE 2011 MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION


DETAIL E-1 SILT FENCE

STANDARD SYMBOL
SF




MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL

U.S. DEPARTMENT OF AGRICULTURE NATURAL RESOURCES CONSERVATION SERVICE 2011 MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION



TURBIDITY CURTAIN CONNECTIONS

Detail Drawing 4.6-A



TURBIDITY CURTAIN CONNECTIONS

Detail Drawing 4.6-B

MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL

U.S. DEPARTMENT OF AGRICULTURE NATURAL RESOURCES CONSERVATION SERVICE 2011 MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION

CONSTRUCTION SPECIFICATIONS


- USE WOOD POSTS 1 1/2 X 1 1/2 X 1/8 INCH (MINIMUM) SQUARE CUT OF SOUND QUALITY HARDWOOD. AS AN ALTERNATIVE TO WOODEN POST USE STANDARD "T" OR "U" SECTION STEEL POSTS WEIGHING NOT LESS THAN 1 POUND PER LINEAR FOOT.
- USE 36 INCH MINIMUM POSTS DRIVEN 16 INCH MINIMUM INTO GROUND NO MORE THAN 6 FEET APART.
- USE WOVEN SLIT FILM GEOTEXTILE AS SPECIFIED IN SECTION H-1 MATERIALS AND FASTEN GEOTEXTILE SECURELY TO UPSLOPE SIDE OF FENCE POSTS WITH WIRE TIES OR STAPLES AT TOP AND MID-SECTION.
- PROVIDE MANUFACTURER CERTIFICATION TO THE AUTHORIZED REPRESENTATIVE OF THE INSPECTION/ENFORCEMENT AUTHORITY SHOWING THAT THE GEOTEXTILE USED MEETS THE REQUIREMENTS IN SECTION H-1 MATERIALS.
- EMBED GEOTEXTILE A MINIMUM OF 8 INCHES VERTICALLY INTO THE GROUND. BACKFILL AND COMPACT THE SOIL ON BOTH SIDES OF FABRIC.
- WHERE TWO SECTIONS OF GEOTEXTILE ADJOIN: OVERLAP, TWIST, AND STAPLE TO POST IN ACCORDANCE WITH THIS DETAIL.
- EXTEND BOTH ENDS OF THE SILT FENCE A MINIMUM OF FIVE HORIZONTAL FEET UPSLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT TO PREVENT RUNOFF FROM GOING AROUND THE ENDS OF THE SILT FENCE.
- REMOVE ACCUMULATED SEDIMENT AND DEBRIS WHEN BULGES DEVELOP IN SILT FENCE OR WHEN SEDIMENT REACHES 25% OF FENCE HEIGHT. REPLACE GEOTEXTILE IF TORN. IF UNDERMINING OCCURS, REINSTALL FENCE.

MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL

U.S. DEPARTMENT OF AGRICULTURE NATURAL RESOURCES CONSERVATION SERVICE 2011 MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION

WOODY DEBRIS DETAIL


Not to Scale



TYPICAL TREE PROTECTION FENCE DETAIL

BLAZE ORANGE FENCE PROFILE

Not to Scale



TYPICAL TREE PROTECTION FENCE DETAIL

INSTALLATION SEQUENCE

- FOREST PROTECTION DEVICE ONLY
- PROTECTION AREA(S) WILL BE SET AS PART OF THE REVIEW & DESIGN PROCESS.
- BOUNDARIES OF RETENTION AREA SHOULD BE STAKED AND FLAGGED PRIOR TO INSTALLING DEVICE.
- ROOT DAMAGE SHOULD BE AVOIDED.
- PROTECTIVE SIGNAGE MAY ALSO BE USED.
- DEVICE SHOULD BE MAINTAINED THROUGHOUT CONSTRUCTION.

NO.	BY	DATE	DESCRIPTION


NO.	BY	DATE	DESCRIPTION

Survey:
Sustainable Science, LLC
Sustainable Science, LLC
410 S. Second Street
Denton, MD 21629
phone: (410) 924-4316

Prepared for/Applicant:
Hillsmere Shores Improvement Association (HSIA)
P.O. Box 3485
Annapolis, MD 21043

Prepared by:
Environmental Systems Analysis, Inc.
Natural Resources Management
Ecological Restoration
2141 Priest Bridge Drive, Suite 1
Crofton, Maryland 21114

SEDIMENT & EROSION CONTROL DETAILS
HILLSMERE SHORES COASTAL RESILIENCY PROJECT
MAP 0057, GRID 0013, PARCEL 0159, SUBDIVISION 412
2ND ELECTION DISTRICT, ANNE ARUNDEL COUNTY, MD
SCALE:
DATE: APRIL, 2023
ESA PROJECT NAME: 22587
HILLSMERE MARINA LIVING SHORELINE
SHEET: 4 of 7



LEGEND

- EX. PROPERTY BNDRY
- EX. MAJOR CONTOUR
- EX. MINOR CONTOUR
- x- EX. FENCE LINE
- EX. TREE / SHRUB LINE
- ⊙ ⊙ ⊙ EX. VEGETATION (ALL EXISTING TREES & GRASSES TO REMAIN)
- ▨ EX. ROCK / REVETMENT
- EX. MHWL / MLWL
- 0 --- PROPOSED MAJOR CONTOUR
- 1 --- PROPOSED MINOR CONTOUR
- ▨ EX. PROPOSED ROCK STRUCTURE
- ▨ SAND / COBBLE FILL
- LOD LIMIT OF DISTURBANCE
- TPF TREE PROTECTION FENCE
- TC TURBIDITY CURTAIN
- STABILIZED CONSTRUCTION ENTRANCE
- ▨ DUNE GRASSES
- ▨ HIGH MARSH
- ▨ CONSERVATION PLANTING
- ▨ LOW MARSH
- ⊙ ⊙ ⊙ PROPOSED SHRUBS

LANDSCAPE SCHEDULE

LOW MARSH (913 S.F.)					
QTY.	SCIENTIFIC NAME	COMMON NAME	CONDITION	SIZE	SPACING
469	SPARTINA PATENS	SALT MARSH CORD GRASS	PLUG	-	18" O.C.

HIGH MARSH (13,763 S.F.)					
QTY.	SCIENTIFIC NAME	COMMON NAME	CONDITION	SIZE	SPACING
6117	SPARTINA PATENS	SALT MARSH CORD GRASS	PLUG	-	18" O.C.

DUNE GRASSES (4282 S.F.)					
QTY.	SCIENTIFIC NAME	COMMON NAME	CONDITION	SIZE	SPACING
475	AMMOPHILA BREVILIGULATA	AMERICAN BEACHGRASS	PLUG	-	18" O.C.
475	PANICUM AMARUM	COASTAL PANIC GRASS	PLUG	-	18" O.C.
475	PANICUM VIRGATUM	SWITCHGRASS	PLUG	-	18" O.C.
475	SOLIDAGO SEMPERVIRENS	SEASIDE GOLDENROD	PLUG	-	18" O.C.

NOTES:
 1. S. PATENS AND A. BREVILIGULATA SHALL BE PLANTED 2 INCHES BELOW THE NURSERY CROWN DEPTH.
 2. P. AMARUM, P. VIRGATUM, AND S. SEMPERVIRENS SHALL BE PLANTED 0.5-1 INCH BELOW NURSERY CROWN DEPTH.

CONSERVATION PLANTINGS (3,730 S.F.)					
QTY.	SCIENTIFIC NAME	COMMON NAME	CONDITION	SIZE	SPACING
TREES					
2	PINUS THUNBERGII (PT)	JAPANESE BLACK PINE	CONT.	5 GAL.	AS SHOWN
SHRUBS					
5	ARONIA ARBUTIFOLIA (AA)	RED CHOKEBERRY	CONT.	3 GAL.	AS SHOWN
5	ILEX GLABRA (IG)	INKBERRY	CONT.	3 GAL.	AS SHOWN
5	ITEA VIRGINICA (IV)	VIRGINIA SWEETSPIRE	CONT.	3 GAL.	AS SHOWN
HERBACEOUS PLANTS					
75	ASCLEPIAS TUBEROSA	BUTTERFLY WEED	CONT.	QUART	24" O.C.
75	EUPATORIUM FISTULOSUM	JOE-PYE-WEED	CONT.	QUART	24" O.C.
75	HELIANTHUS ANGSTIFOLIUS	SWAMP SUNFLOWER	CONT.	QUART	24" O.C.
75	MONARDA DIDYMA	BEE BALM	CONT.	QUART	24" O.C.
75	VERNONIA NOVEBORACENSIS	NEW YORK IRONWEED	CONT.	QUART	24" O.C.
GRASSES					
75	ANDROPOGON GERDII	BIG BLUESTEM	CONT.	1 GAL.	24" O.C.
75	CAREX STRICTA	TUSSOCK SEDGE	CONT.	1 GAL.	24" O.C.
16	PANICUM VIRGATUM (PV)	SWITCHGRASS	CONT.	1 GAL.	AS SHOWN
75	SORGHASTRUM NUTANS	INDIANGRASS	CONT.	1 GAL.	24" O.C.


NOTES:
 1. EXISTING VEGETATION IS TO REMAIN. SUPPLEMENT EXISTING VEGETATION WITH THE ABOVE SPECIES LOCATED IN CLUSTERS OF SIMILAR SPECIES.

REVISIONS		
NO.	BY	DATE

Survey:

 Sustainable Science, LLC
 410 S. Second Street
 Denton, MD 21629
 phone: (410) 924-4316

Prepared for/Applicant:
 Hillsmere Shores Improvement Association (HSIA)
 P.O. Box 3485
 Annapolis, MD 21043

Prepared by:

 Environmental Systems Analysis, Inc.
 Natural Resources Management
 Ecological Restoration
 2141 Priest Bridge Drive, Suite 1
 Crofton, Maryland 21114

PLANTING PLAN
HILLSMERE SHORES COASTAL RESILIENCY PROJECT
 MAP 0057, GRID 0013, PARCEL 0159, SUBDIVISION 412

2ND ELECTION DISTRICT, ANNE ARUNDEL COUNTY, MD

SCALE: 1"=30'

DATE: APRIL, 2023
 ESA PROJECT NAME: 22587
 HILLSMERE MARINA LIVING SHORELINE
 SHEET: 6 of 7

GENERAL PLANTING NOTES

1. THE LANDSCAPE CONTRACTOR SHALL NOTIFY THE RESTORATION SPECIALIST OF THE SCHEDULED DATE FOR COMMENCEMENT OF PLANTING SO THAT ALL MATERIALS AND PLANTING METHODS MAY BE INSPECTED AND APPROVED BY THE RESTORATION SPECIALIST. NO PLANTS SHALL BE INSTALLED WITHOUT THE RESTORATION SPECIALIST ON SITE.
2. ALL PLANTS SHALL BE PLACED WITHIN THE LIMITS OF DISTURBANCE.
3. THE LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES AND FOR UNDERSTANDING AND HONORING PROPERTY BOUNDARIES. ANY UTILITIES OR OTHER PROPERTY DAMAGED DURING PLANTING SHALL BE CORRECTED BY THE CONTRACTOR AT THE CONTRACTOR'S EXPENSE.
4. GIVEN THE LARGE QUANTITY OF PLUGS, CONTACT THE NURSERY WELL IN ADVANCE OF PLANTING TO ENSURE AVAILABILITY.

STANDARDS

1. ALL PLANT MATERIAL SHALL CONFORM TO THE CURRENT ISSUE OF THE AMERICAN STANDARD FOR NURSERY STOCK PUBLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN AND AS SPECIFIED BELOW.
2. ALL CONTAINER STOCK SHALL BE NURSERY-GROWN WITHIN A 200-MILE RADIUS OF THE SITE. PLANT MATERIALS, WITH THE EXCEPTION OF LIVE STAKES, THAT ARE COLLECTED FROM THE WILD WILL BE REJECTED.
3. PLANT MATERIAL SHALL BE OBTAINED FROM NURSERIES THAT HAVE BEEN INSPECTED AND CERTIFIED BY STATE PLANT INSPECTORS.
4. THE ROOT SYSTEM OF CONTAINER GROWN PLANTS SHALL BE WHITE, WELL DEVELOPED, AND WELL-DISTRIBUTED THROUGHOUT THE CONTAINER WITH THE ROOTS VISIBLY EXTENDING TO THE INSIDE FACE OF THE GROWING CONTAINER.
5. IF IN LEAF, THE PLANTS SHALL APPEAR HEALTHY WITH NO LEAF SPOTS, LEAF DAMAGE, LEAF DISCOLORATION, LEAF WILTING OR EVIDENCE OF INSECTS ON THE PLANT.
6. THERE SHALL BE NO CHANGE IN THE QUANTITY, SIZE OR SPECIES OF SCHEDULED PLANT MATERIAL WITHOUT THE PRIOR APPROVAL OF THE RESTORATION SPECIALIST.

STORAGE AND DELIVERY

1. AFTER BEING DELIVERED TO THE JOB SITE, PLANTS SHALL BE STORED IN A COOL, SHADY LOCATION. PLANT ROOT MASSES SHALL BE KEPT MOIST WITH PERIODIC WATERING UNTIL THE TIME OF PLANTING.
2. SOIL ROOT MASSES SHALL BE THOROUGHLY MOIST UPON DELIVERY TO THE SITE. DRY OR LIGHT WEIGHT PLANTS SHALL BE REJECTED. IF THE SOIL/ROOT MASSES ARE SUBSTANTIALLY SMALLER THAN THE SPECIFIED CONTAINER SIZE AND LOOSE SOIL EXISTS ON THE BOTTOM OF THE CONTAINERS, THE PLANTS SHALL BE REJECTED.
3. ALL REJECTED MATERIAL SHALL BE IMMEDIATELY REMOVED FROM THE SITE.

MAINTENANCE AND GUARANTEE

1. PLANT MATERIAL SHALL BE MAINTAINED BY THE LANDSCAPE CONTRACTOR FOR ONE YEAR FROM THE DATE OF INITIAL INSPECTION AND ACCEPTANCE OF THE PLANTING BY THE RESTORATION SPECIALIST. MAINTENANCE SHALL INCLUDE ALL WATERING, FERTILIZATION AND ANIMAL REPELLENTS NECESSARY TO ENSURE THE SURVIVAL AND GROWTH OF THE PLANTS.
2. THE LANDSCAPE CONTRACTOR SHALL GUARANTEE THAT 85% OF THE PLANTED SHRUBS, 75% OF THE HERBACEOUS STOCK SHALL BE ALIVE AND HEALTHY ONE YEAR AFTER THE INITIAL INSPECTION AND ACCEPTANCE BY THE RESTORATION SPECIALIST. AT THE END OF THIS PERIOD, THE RESTORATION SPECIALIST SHALL CONDUCT A FINAL INSPECTION WITH THE LANDSCAPE CONTRACTOR. ALL PLANT MATERIAL EXCEEDING THOSE THRESHOLDS SHALL BE REPLACED BY THE LANDSCAPE CONTRACTOR AT THE CONTRACTOR'S EXPENSE. THIS GUARANTEE SHALL COVER ALL DAMAGES EXCEPT VANDALISM, FIRE, AND FLOOD, AND ANIMAL PREDATION.
3. PLANT MATERIAL WHICH IS 25% DEAD OR MORE SHALL BE CONSIDERED DEAD.
4. PLANT MATERIAL REPLACEMENTS SHALL BE OF THE SAME SIZE, TYPE AND VARIETY AS THE PLANTS SPECIFIED IN THE PLANTING SCHEDULE OR AS THE APPROVED SUBSTITUTES FOR THE ORIGINAL PLANTING.
5. PLANTS SHALL BE FURNISHED AND PLANTED AS SPECIFIED IN THESE PLANS.


GENERAL PLANTING PROCEDURES

1. PLANTING SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST EDITION OF "THE LANDSCAPE CONTRACTORS ASSOCIATION'S LANDSCAPE SPECIFICATION GUIDELINES" AND AS SPECIFIED BELOW.
2. CONTAINER STOCK MAY BE INSTALLED FROM SEPTEMBER 1 TO DECEMBER 1 AND FROM MARCH 15 TO JUNE 15. PLANTING SHALL NOT BE PERFORMED OUTSIDE OF THESE DATES WITHOUT THE EXPRESSED PERMISSION OF THE RESTORATION SPECIALIST. IN ADDITION, PLANTING SHALL NOT OCCUR IN SUB-FREEZING TEMPERATURES, WHEN THE GROUND IS FROZEN, OR WHEN THE SOIL IS TOO DRY OR WET, OR OTHERWISE IN A CONDITION NOT GENERALLY ACCEPTED AS SATISFACTORY FOR PLANTING.
3. HERBACEOUS PLUGS SHALL BE PLANTED AT LEAST TWO WEEKS AFTER GRADING AND BETWEEN MAY 1 TO SEPTEMBER 30.


CONTAINER STOCK

1. FOR TREES AND SHRUBS, EXCAVATE A HOLE AT LEAST 12" WIDER THAN THE WIDTH OF THE ROOTBALL AND TO A DEPTH WHICH LEAVES APPROXIMATELY 1/4 OF THE ROOTBALL ABOVE THE EXISTING GRADE. FOR HERBACEOUS STOCK, EXCAVATE THE HOLE AT LEAST 1" WIDER THAN THE WIDTH OF THE ROOT MASS.
2. REMOVE THE PLANT EITHER BY CUTTING OR INVERTING THE CONTAINER.
3. TO ENCOURAGE THE OUTWARD GROWTH OF THE ROOTS FOR TREES AND SHRUBS, MAKE 4 TO 5, 1" DEEP CUTS THE LENGTH OF THE ROOT BALL WITH A SHARP KNIFE OR BLADE.
4. INSTALL PLANT IN THE CENTER OF THE HOLE AT FINISHED LANDSCAPE GRADE. ADD OSMOCOTE 18-6-12 SLOW RELEASE FERTILIZER TO THE HOLE PER PRODUCT SPECIFICATIONS AND INSTALL PLANT IN CENTER OF THE HOLE AT FINISHED LANDSCAPE GRADE.
5. BACKFILL PLANTING HOLE WITH TWO THIRDS EXISTING SOIL AND ONE THIRD COMPOST (SEE MATERIAL SPECS SHEET 5) AND HYDROPHILIC GEL PER PRODUCT SPECIFICATIONS.
6. ANY SURPLUS SOIL WHICH REMAINS AFTER PLANTING SHALL BE USED TO CREATE A SMALL MOUND AROUND THE EDGE OF THE PLANTING HOLE TO HOLD WATER DURING WATERING OPERATIONS.
7. THOROUGHLY WATER EACH PLANT AFTER INSTALLATION. WATERING SHALL BE PERFORMED EVEN IF IT IS RAINING. A SECOND WATERING MAY BE NECESSARY TO INSURE SATURATION OF THE ROOTBALL AND ELIMINATION OF THE AIR POCKETS.
8. PRUNE ANY AND ALL TREE BRANCHES THAT ARE DEAD, DISEASED, DAMAGED, OR CONFLICTING.
9. REMOVE ALL TAGS, LABELS, STRINGS AND WIRE.


TYPICAL DECIDUOUS PLANTING DETAIL
CONTAINER / B&B




TYPICAL SHRUB / HERBACEOUS PLANTING DETAIL
CONTAINER / B&B



TYPICAL HERBACEOUS PLUG PLANTING DETAIL



GOOSE EXCLUSIONARY FENCING
NOT TO SCALE



1. INSTALL 5' WOOD POSTS 1.5-FOOT IN EXISTING SOIL ON A 10' GRID.
2. NYLON STRING SHALL BE INSTALLED TAUT AND WRAPPED ONCE AROUND EACH POST.
3. ROPE SHALL BE INSTALLED A MAXIMUM OF 6 INCHES OFF THE GROUND.
4. ROPE SHALL BE EVENLY SPACED OVER THE 4 STRANDS.
5. THE TOP STRAND SHALL BE CROSSED OVER THE GRID AS SHOWN IN THE PLAN VIEW.

April 2023 FILE: T:\NEWPROJ\2022\22587 Hillsmere Marina Shoreline\CAO\Plans\Grading Permit Plans\Sheet 6 - Planting Plan.dwg

REVISIONS		
NO.	BY	DATE

Survey:



Sustainable Science, LLC
410 S. Second Street
Denton, MD 21629
phone: (410) 924-4316

Prepared for/Applicant:

Hillsmere Shores Improvement Association (HSIA)
P.O. Box 3485
Annapolis, MD 21043

Prepared by:



Environmental Systems Analysis, Inc.
Natural Resources Management
Ecological Restoration
2141 Priest Bridge Drive, Suite 1
Crofton, Maryland 21114

PLANTING DETAILS

HILLSMERE SHORES COASTAL RESILIENCY PROJECT
MAP 0057, GRID 0013, PARCEL 0159, SUBDIVISION 412

2ND ELECTION DISTRICT, ANNE ARUNDEL COUNTY, MD

SCALE:
DATE: APRIL, 2023
ESA PROJECT NAME: 22587
HILLSMERE MARINA LIVING SHORELINE
SHEET: 7 of 7